
# RESIDENTIAL SITE PLAN 242 SOUTH MAIN ST. TAX MAP U4, LOT 69

# CIVIL ENGINEERS:





# LAND SURVEYOR:



# LANDSCAPE ARCHITECT




&company Newmarket, NH 03857

www.woodburnandcompany.com www.houzz.com/pro/robwoodburn

# WETLAND / SOIL CONSULTANT:

GOVE ENVIRONMENTAL SERVICES INC. 8 CONTINENTAL DRIVE, BLDG 2 UNIT H EXETER, NH 03833 1-603-778-0644





PLAN INDEX TITLE SHEET SUBDIVISION PLANS EXISTING CONDITIONS PLANS OVERALL SITE PLAN PARKING/PAVEMENT PLAN GRADING & DRAINAGE PLAN UTILITY/LIGHTING PLAN CONSTRUCTION DETAILS 7 - 10EROSION & SEDIMENT CONTROL DETAILS LANDSCAPE PLANS

### PLAN SET LEGEND


OVERHEAD ELEC. LINE 5/8" REBAR DRILL HOLE DRAINAGE LINE CONC. BOUND SEWER LINE UTILITY POLE WATER LINE DRAIN MANHOLE STONE WALL SEWER MANHOLE TREE LINE EXISTING LIGHT POLE ABUT. PROPERTY LINES WATER SHUT OFF EXIST. PROPERTY LINES PINES, ETC. BUILDING SETBACK LINES MAPLES, ETC. EXIST. CONTOUR PROP. SPOT GRADE PROP. CONTOUR SINGLE POST SIGN SOIL LINES . . . . . . . . . . . . . . . . . . TEST PIT W/NO. SILT FENCING \_\_\_\_\_\_

OWNER/APPLICANT: DR LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857

REQUIRED PERMITS NHDES SEWER EXTENSION # NHDES DW/GW PERMIT # LOCAL DRIVEWAY PERMIT#

PLANNING	BOARD	APPROVAL	BLOCK

REVISIONS PER REVIEW COMMENTS	10-18-23
REVISIONS PER REVIEW COMMENTS	8-16-23



CONDUCTED AT THE TOWN OF NEWMARKET, THE STATE OF NEW HAMPSHIRE DEPARTMENT OF TRANSPORTATION AND ROCKINGHAM COUNTY REGISTRY OF DEEDS.

13. FINAL MONUMENTATION MAY BE DIFFERENT THAN THE PROPOSED MONUMENTATION SHOWN HEREON, DUE TO THE FACT THAT SITE CONDITIONS WILL DICTATE THE ACTUAL LOCATION AND TYPE OF MONUMENTS INSTALLED IN THE FIELD. PLEASE REFER TO EITHER THE "MONUMENTATION LOCATION PLAN" TO BE RECORDED OR CONTACT DOUCET SURVEY. FOR CLARIFICATION OF MONUMENTS SET. (A RECORDED PLAN WILL BE PRODUCED AT THE DISCRETION OF DOUCET SURVEY).

### REFERENCE PLANS:

MAX. BUILDING COVERAGE -- %

VERY POORLY DRAINED 50 ft.

ZONING INFORMATION LISTED HEREON IS BASED ON THE TOWN OF NEWMARKET ZONING ORDINANCE

REGULATIONS APPLY, AND REFERENCE IS HEREBY MADE TO THE EFFECTIVE ZONING ORDINANCE. THE

FIELD SURVEY PERFORMED BY DOUCET SURVEY DURING AUGUST, SEPTEMBER, AND OCTOBER 2022

USING A TRIMBLE S5 TOTAL STATION AND A TRIMBLE R10 SURVEY GRADE GPS WITH A TRIMBLE

TSC3 DATA COLLECTOR AND A TRIMBLE DINI DIGITAL LEVEL. TRAVERSE ADJUSTMENT BASED ON

HORIZONTAL DATUM BASED ON NAD83(2011) NEW HAMPSHIRE STATE PLANE COORDINATE ZONE

JURISDICTIONAL WETLANDS DELINEATED BY JAMES P. GOVE, CWS 051, CSS 004 OF GOVE

•REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL:

ENVIRONMENTAL SERVICES, INC. DURING AUGUST 2022 ACCORDING TO THE:

NORTHCENTRAL AND NORTHEAST REGION, VERSION 2.0, JANUARY 2012.

(2800) DERIVED FROM REDUNDANT GPS OBSERVATIONS UTILIZING THE KEYNET GPS VRS NETWORK.

•US ARMY COPRS OF ENGINEERS WETLANDS DELINEATION MANUAL, TECHNICAL REPORT Y-87-1

•FIELD INDICATORS FOR IDENTIFYING DYDRIC SOILS IN NEW ENGLAND, VERSION 4, NEW ENGLAND

PRIME WETLANDS SHOWN HEREON BASED ON "TOWN OF NEWMARKET, NH PRIME WETLANDS MAP 2:

NORTH-CENTRAL SECTION" PRODUCED BY THE TOWN OF NEWMARKET MARCH 24, 2004 UPDATED BY

DATED 12/08/2020 AS AVAILABLE ON THE TOWN WEBSITE ON 05/17/2023. ADDITIONAL

LAND OWNER IS RESPONSIBLE FOR COMPLYING WITH ALL APPLICABLE MUNICIPAL, STATE AND

WETLAND SETBACKS POORLY DRAINED


FEDERAL REGULATIONS

LEAST SQUARE ANALYSIS.

HYDRIC SOILS TECHNICAL COMMITTEE.

STRAFFORD RPC JANUARY 8, 2013.


- 1. "D.W. HOYT DEVELOPMENT MAPLECREST NEWMARKET N.H." DATED OCTOBER 4, 1951 BY H.V. SHEAHAN C.E. R.C.R.D. PLAN 01752.
- 2. "D.W. HOYT HOUSING PROJECT 30 MAIN STREET NEWMARKET N.H." DATED JULY 1951 BY H.V. SHEAHAN R.C.R.D. PLAN 01753.
- 3. "TAX MAP U-2 LOT 68 CONDOMINIUM SITE PLAN 258 WADLEIGH FALLS RD., A-B 258 WADLEIGH FALLS ROAD NEWMARKET, NEW HAMPSHIRE COUNTY OF ROCKINGHAM OWNED BY NORTHPOINT REALTY, INC." DATED MAY 28, 2021 REVISED 6/7/2021 AND 7/20/2021 BY TFMORAN R.C.R.D. PLAN D-42885.
- 4. "SUBDIVISION OF LAND OF JOHN CARPENTER IN NEWMARKET N.H." DATED 11/5/76 BY MOULTON ENGINEERING CO. R.C.R.D. PLAN D-6451.
- 5. "SUBDIVISION PLAN FOR AMERICAN LAND DEVELOPMENT INC. WOOD HAVEN PHASE II IN NEWMARKET, N.H." DATED NOV. 2, 1981 BY KIMBALL CHASE COMPANY R.C.R.D PLAN D-10912.



I CERTIFY THAT THIS SURVEY AND PLAN WERE PREPARED BY ME OR BY THOSE UNDER MY DIRECT SUPERVISION AND FALLS UNDER THE URBAN SURVEY CLASSIFICATION OF THE NH CODE OF ADMINISTRATIVE RULES OF THE BOARD OF LICENSURE FOR LAND SURVEYORS. I CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. RANDOM TRAVERSE SURVEY BY TOTAL STATION, WITH A PRECISION GREATER THAN 1:15,000.

 Bu Ji	L.L.S. #1058
 AUGUST 22, 2023	DATE

THE CERTIFICATIONS SHOWN HEREON ARE INTENDED TO MEET REGISTRY OF DEED REQUIREMENTS AND ARE NOT A CERTIFICATION TO TITLE OR OWNERSHIP OF PROPERTY SHOWN. OWNERS OF ADJOINING PROPERTIES ARE ACCORDING TO CURRENT TOWN ASSESSORS RECORDS.



LOCATION MAP (n.t.s.)





D.R. LEMIEUX BUILDERS, LLC TAX MAP U4, LOT 69 242 SOUTH MAIN STREET NEWMARKET, NEW HAMPSHIRE


SUBDIVISION PLAN

1	8/22/23	REVISE PROPOSED LOT	J.R.F
NO.	DATE	DESCRIPTION	BY

	DRAWN BY:	M.T.L.	DATE: MAY 23, 2023	
	CHECKED BY:	B.T.	drawing no. 7630D	
	JOB NO.	7630	SHEET 1 OF 2	
ļ	OOD NO.		OHEET OF	-



Serving Your Professional Surveying & Mapping Needs 102 Kent Place, Newmarket, NH 03857 (603) 659-6560 Offices in Bedford & Keene, NH and Kennebunk, ME http://www.doucetsurvey.com



VERY POORLY DRAINED

FENCE POST

I.P.F.

RET. WALL

DOUBLE YELLOW LINE

EDGE OF PAVEMENT

IRON PIPE FOUND

SINGLE WHITE LINE

RETAINING WALL

PIPE/ROD FOUND


— — — — — 25' WETLAND SETBACK LINE — POORLY DRAINED


DRILL HOLE FOUND (D.H.F.)

5/8" REBAR W/ID CAP TO BE SET

4"X4" GRANITE BOUND TO BE SET

BARBED WIRE FOUND ON GROUND





I CERTIFY THAT THIS SURVEY AND PLAN WERE PREPARED BY ME OR BY THOSE UNDER MY DIRECT SUPERVISION AND FALLS UNDER THE URBAN SURVEY CLASSIFICATION OF THE NH CODE OF ADMINISTRATIVE RULES OF THE BOARD OF LICENSURE FOR LAND SURVEYORS. I CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. RANDOM TRAVERSE SURVEY BY TOTAL STATION, WITH A PRECISION GREATER THAN 1:15,000.

L.L.S. #1058

AUGUST 22, 2023 DATE

THE CERTIFICATIONS SHOWN HEREON ARE INTENDED TO MEET REGISTRY OF DEED REQUIREMENTS AND ARE NOT A CERTIFICATION TO TITLE OR OWNERSHIP OF PROPERTY SHOWN. OWNERS OF ADJOINING PROPERTIES ARE ACCORDING TO CURRENT TOWN ASSESSORS RECORDS.

APPROVED BY THE NEWMARKET PLANNING BOARD

CHAIRPERSON DATE






SUBDIVISION PLAN
FOR
D.R. LEMIEUX BUILDERS, LLC
OF
TAX MAP U4, LOT 69
242 SOUTH MAIN STREET
NEWMARKET, NEW HAMPSHIRE

1	8/22/23	REVISE PROPOSED LOT	J.R.P
NO.	DATE	DESCRIPTION	BY

DRAWN BY:	M.T.L.	DATE: MAY 23, 2023
CHECKED BY:	B.T.	DRAWING NO. 7630D
JOB NO.	7630	SHEET 2 OF 2



Serving Your Professional Surveying & Mapping Needs 102 Kent Place, Newmarket, NH 03857 (603) 659-6560 Offices in Bedford & Keene, NH and Kennebunk, ME http://www.doucetsurvey.com



TOTAL PARCEL AREA:
 337,899 SQ. FT. OR 7.76 AC.
 OWNER OF RECORD:
 D.R. LEMIEUX BUILDERS, LLC 76 EXETER ROAD NEWMARKET. NH 03857

OBSERVATIONS UTILIZING THE KEYNET GPS VRS NETWORK.

HYDRIC SOILS TECHNICAL COMMITTEE.

4. FIELD SURVEY PERFORMED BY DOUCET SURVEY DURING AUGUST, SEPTEMBER, AND OCTOBER 2022 USING A TRIMBLE S5 TOTAL STATION AND A TRIMBLE R10 SURVEY GRADE GPS WITH A TRIMBLE TSC3 DATA COLLECTOR AND A TRIMBLE DINI DIGITAL LEVEL. TRAVERSE ADJUSTMENT BASED ON LEAST SQUARE ANALYSIS.

R.C.R.D. BOOK 6439, PAGE 1906

- 5. HORIZONTAL DATUM BASED ON NAD83(2011) NEW HAMPSHIRE STATE PLANE COORDINATE ZONE (2800)
- 6. VERTICAL DATUM IS BASED ON APPROXIMATE NAVD88(GEOID18) (±.2') DERIVED FROM REDUNDANT GPS

DERIVED FROM REDUNDANT GPS OBSERVATIONS UTILIZING THE KEYNET GPS VRS NETWORK.

- 8. JURISDICTIONAL WETLANDS DELINEATED BY JAMES P. GOVE, CWS 051, CSS 004 OF GOVE ENVIRONMENTAL SERVICES, INC. DURING AUGUST 2022 ACCORDING TO THE:

  •US ARMY COPRS OF ENGINEERS WETLANDS DELINEATION MANUAL, TECHNICAL REPORT Y-87-1
- •REGIONAL SUPPLEMENT TO THE CORPS OF ENGINEERS WETLAND DELINEATION MANUAL:
  NORTHCENTRAL AND NORTHEAST REGION, VERSION 2.0, JANUARY 2012.
  •FIELD INDICATORS FOR IDENTIFYING DYDRIC SOILS IN NEW ENGLAND, VERSION 4, NEW ENGLAND
- 9. FLOOD HAZARD ZONE: "X" & "A", PER FIRM MAP #33015C0230F, DATED 1/29/2021.
- 10. PROPER FIELD PROCEDURES WERE FOLLOWED IN ORDER TO GENERATE CONTOURS AT 2' INTERVALS. ANY MODIFICATION OF THIS INTERVAL WILL DIMINISH THE INTEGRITY OF THE DATA, AND DOUCET SURVEY. WILL NOT BE RESPONSIBLE FOR ANY SUCH ALTERATION PERFORMED BY THE USER.
- 11. UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON OBSERVED PHYSICAL EVIDENCE AND PAINT MARKS FOUND ON—SITE. NO UTILITIES WERE MARKED AS PART OF THIS SURVEY. THE WATER LINE AS SHOWN HEREON WAS PROVIDED BY BEALS ASSOCIATES, PLLC.

- 12. THE ACCURACY OF MEASURED UTILITY INVERTS AND PIPE SIZES/TYPES IS SUBJECT TO NUMEROUS FIELD CONDITIONS, INCLUDING; THE ABILITY TO MAKE VISUAL OBSERVATIONS, DIRECT ACCESS TO THE VARIOUS ELEMENTS, MANHOLE CONFIGURATION, ETC.
- 13. THE INTENT OF THIS PLAN IS TO SHOW THE LOCATION OF BOUNDARIES IN ACCORDANCE WITH AND IN RELATION TO THE CURRENT LEGAL DESCRIPTION, AND IS NOT AN ATTEMPT TO DEFINE UNWRITTEN RIGHTS, DETERMINE THE EXTENT OF OWNERSHIP, OR DEFINE THE LIMITS OF TITLE.
- 14. SOUTH MAIN STREET/WADLEIGH FALLS ROAD (ROUTE 152) RIGHT OF WAY IS FOUR RODS (66') IN WIDTH, SEE S.R. SHEET 5-49 (BOOK 18, PAGE 849) ON FILE AT THE STATE OF NEW HAMPSHIRE ARCHIVES. THE RIGHT OF WAY AS SHOWN HEREON IS BASED ON THE EXISTING CENTERLINE AND MONUMENTS FOUND IN THE FIELD.
- 15. ALL UNDERGROUND UTILITIES (ELECTRIC, GAS, TEL. WATER, SEWER DRAIN SERVICES) ARE SHOWN IN SCHEMATIC FASHION, THEIR LOCATIONS ARE NOT PRECISE OR NECESSARILY ACCURATE. NO WORK WHATSOEVER SHALL BE UNDERTAKEN USING THIS PLAN TO LOCATE THE ABOVE SERVICES. CONSULT WITH THE PROPER AUTHORITIES CONCERNED WITH THE SUBJECT SERVICE LOCATIONS FOR INFORMATION REGARDING SUCH. CALL DIG—SAFE AT 1—888—DIG—SAFE.
- 16. PRIME WETLANDS SHOWN HEREON BASED ON "TOWN OF NEWMARKET, NH PRIME WETLANDS MAP 2: NORTH-CENTRAL SECTION" PRODUCED BY THE TOWN OF NEWMARKET MARCH 24, 2004 UPDATED BY STRAFFORD RPC JANUARY 8, 2013.
- 17. SITE SPECIFIC SOILS SHOWN HEREON WITHIN THE TECHNICAL STANDARDS OF THE NATIONAL COOPERATIVE SOIL SURVEY. IT IS A SPECIAL PURPOSE PRODUCT, INTENDED FOR INFILTRATION REQUIREMENTS BY THE NH DES ALTERATION OF TERRAIN BUREAU. IT WAS PRODUCED BY A PROFESSIONAL SOIL SCIENTIST, AND IS NOT A PRODUCT OF THE USDA NATURAL RESOURCES CONSERVATION SERVICE. THERE IS A REPORT THAT ACCOMPANIES THIS MAP.
- 18. THE SITE SPECIFIC SOIL MAP (SSSM) WAS PRODUCED 04-10-2023, AND WAS PREPARED BY JAMES P. GOVE, CSS # 004, GOVE ENVIRONMENTAL SERVICES, INC. THE SURVEY AREA IS LOCATED AT 242 SOUTH MAIN STREET, NEWMARKET, NH. SOILS WERE IDENTIFIED WITH THE NEW HAMPSHIRE STATE-WIDE NUMERICAL SOILS LEGEND, USDA NRCS, DURHAM, NH. ISSUE # 10, JANUARY 2011. THE NUMERIC LEGEND WAS AMENDED TO IDENTIFY THE CORRECT SOIL COMPONENTS OF THE COMPLEX.

SSSM SYM. SSSM MAP NAME HISS NO. HYDRO. SOIL GROUP
38 ELDRIDGE LOAMY SAND 343 C
538 SQUAMSCOTT LOAMY SAND 543 C
134 MAYBID MUCKY SILT 643 D

SLOPE PHASE:

0-8%=B, 8-15%=C, 15-25%=D, 25%+=E

### DEFEDENCE DIANG.

- 1. "D.W. HOYT DEVELOPMENT MAPLECREST NEWMARKET N.H." DATED OCTOBER 4, 1951 BY H.V. SHEAHAN C.E. R.C.R.D. PLAN 01752.
- 2. "D.W. HOYT HOUSING PROJECT 30 MAIN STREET NEWMARKET N.H." DATED JULY 1951 BY H.V. SHEAHAN R.C.R.D. PLAN 01753.
- 3. "TAX MAP U-2 LOT 68 CONDOMINIUM SITE PLAN 258 WADLEIGH FALLS RD., A-B 258 WADLEIGH FALLS ROAD NEWMARKET, NEW HAMPSHIRE COUNTY OF ROCKINGHAM OWNED BY NORTHPOINT REALTY, INC." DATED MAY 28, 2021 REVISED 6/7/2021 AND 7/20/2021 BY TFMORAN R.C.R.D. PLAN D-42885.
- 4. "SUBDIVISION OF LAND OF JOHN CARPENTER IN NEWMARKET N.H." DATED 11/5/76 BY MOULTON ENGINEERING CO. R.C.R.D. PLAN D-6451.
- 5. "SUBDIVISION PLAN FOR AMERICAN LAND DEVELOPMENT INC. WOOD HAVEN PHASE II IN NEWMARKET, N.H." DATED NOV. 2, 1981 BY KIMBALL CHASE COMPANY R.C.R.D PLAN D-10912.

SIGNATURE

PURSUANT TO RSA 676:18, III:

I CERTIFY THAT THIS SURVEY PLAT IS NOT A SUBDIVISION PURSUANT TO THIS TITLE AND THAT THE LINES OF STREETS AND WAYS SHOWN ARE THOSE OF PUBLIC OR PRIVATE STREETS OR WAYS ALREADY ESTABLISHED AND THAT NO NEW WAYS ARE SHOWN.

1058

BEVAN

TIMM


I CERTIFY THAT THIS SURVEY AND PLAN WERE PREPARED BY ME OR BY THOSE UNDER MY DIRECT SUPERVISION AND FALLS UNDER THE URBAN SURVEY CLASSIFICATION OF THE NH CODE OF ADMINISTRATIVE RULES OF THE BOARD OF LICENSURE FOR LAND SURVEYORS. I CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. RANDOM TRAVERSE SURVEY BY TOTAL STATION, WITH A PRECISION GREATER THAN 1:15,000."

L.L.S. #1058

OCTOBER 18, 2023

DATE


THE CERTIFICATIONS SHOWN HEREON ARE INTENDED TO MEET REGISTRY OF DEED REQUIREMENTS AND ARE NOT A CERTIFICATION TO TITLE OR OWNERSHIP OF PROPERTY SHOWN. OWNERS OF ADJOINING PROPERTIES ARE ACCORDING TO CURRENT TOWN ASSESSORS RECORDS.




### LOCATION MAP (n.t.s.)

	LINE TABLE	
LINE	BEARING	DISTANCE
L1	N80°55'42"W	79.76'
L2	N73*17'03"W	56.20'
L3	N61°27'44"W	26.56'





### SEE SHEET 2 FOR LEGEND



### **EXISTING CONDITIONS PLAN**

D.R. LEMIEUX BUILDERS, LLC


TAX MAP U4, LOT 69 242 SOUTH MAIN STREET NEWMARKET, NEW HAMPSHIRE


2	10/18/23	ADD WATER LINE - UPDATED NOTE 11	B.T.
1	05/22/23	ADD PRIME WETLANDS & SOILS	M.T.L
NO.	DATE	DESCRIPTION	BY

DRAWN BY:	W.D.C.	DATE: OCTOBER 10, 2022
CHECKED BY:	B.T.	DRAWING NO. 7630B
JOB NO.	7630	SHEET 1 OF 2





Serving Your Professional Surveying & Mapping Needs 102 Kent Place, Newmarket, NH 03857 (603) 659-6560 Offices in Bedford & Keene, NH and Kennebunk, ME http://www.doucetsurvey.com











### PURSUANT TO RSA 676:18, III:

I CERTIFY THAT THIS SURVEY PLAT IS NOT A SUBDIVISION PURSUANT TO THIS TITLE AND THAT THE LINES OF STREETS AND WAYS SHOWN ARE THOSE OF PUBLIC OR PRIVATE STREETS OR WAYS ALREADY ESTABLISHED AND THAT NO NEW WAYS ARE SHOWN.

I CERTIFY THAT THIS SURVEY AND PLAN WERE PREPARED BY ME OR BY THOSE UNDER MY DIRECT SUPERVISION AND FALLS UNDER THE URBAN SURVEY CLASSIFICATION OF THE NH CODE OF ADMINISTRATIVE RULES OF THE BOARD OF LICENSURE FOR LAND SURVEYORS. I CERTIFY THAT THIS SURVEY WAS MADE ON THE GROUND AND IS CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF. RANDOM TRAVERSE SURVEY BY TOTAL STATION, WITH A PRECISION GREATER THAN 1:15,000."



THE CERTIFICATIONS SHOWN HEREON ARE INTENDED TO MEET REGISTRY OF DEED REQUIREMENTS AND ARE NOT A CERTIFICATION TO TITLE OR OWNERSHIP OF PROPERTY SHOWN. OWNERS OF ADJOINING PROPERTIES ARE ACCORDING TO CURRENT TOWN ASSESSORS RECORDS.

### <u>LEGEND</u>

LEGEND	
	EXISTING LOT LINE
	APPROXIMATE ABUTTERS LOT LINE (PER GIS)
	MAJOR CONTOUR LINE MINOR CONTOUR LINE
.00000000000000000000000000000000000000	
v v v	RETAINING WALL
	OVERHEAD WIRE
_	DRAIN LINE SEWER LINE
	TREE LINE
	FEMA FLOOD ZONE LINE
_ · · · _ · · _	EDGE OF DELINEATED WETLAND POORLY DRAINED (SEE NOTE 8)
	EDGE OF DELINEATED WETLAND
	VERY POORLY DRAINED (SEE NOTE 8)
<u> 1111 1111 1111</u>	WETLAND AREA (SEE NOTE 8)
* * * * * * * * * * * * * * * * * * *	PRIME WETLAND AREA (SEE NOTE 16)
	CONCRETE
× 100.0	SPOT GRADE
0	PIPE/ROD FOUND
•	DRILL HOLE FOUND (D.H.F.)
•	5/8" REBAR W/ID CAP OR OTHER SUITABLE MONUMENT TO BE SET
-x-	BARBED WIRE FOUND ON GROUND
Ø	WOODEN POST
<b>⊕</b> €	UTILITY POLE UTILITY POLE & GUY WIRE
	CATCH BASIN
S	SEWER MANHOLE
	FIRE HYDRANT
WV NS	WATER GATE VALVE
<b>°</b> Ö′ ⊠ EM	WATER SHUTOFF VALVE ELECTRIC METER
(M)	MANHOLE
-0	SIGN
• •	POST
<del></del>	MAIL BOX PROPOSED TEST PIT LOCATION
AND THE PARTY OF T	CONIFEROUS TREE
A HELVE	
	DECIDUOUS TREE
	DECIDUOUS BUSH
CONC. D.H.	CONCRETE DRILL HOLE
DIP	DUCTILE IRON PIPE
DYL	DOUBLE YELLOW LINE
EP I.P.F.	EDGE OF PAVEMENT IRON PIPE FOUND
PVC	POLYVINYL CHLORIDE PIPE
RET. WALL	RETAINING WALL
SGC SWL	SLOPED GRANITE CURB SINGLE WHITE LINE
TH SWL	THRESHOLD ELEVATION
T.O.P.	TOP OF PIPE
TYP.	TYPICAL CRANITE CURR
VGC	VERTICAL GRANITE CURB
(VPD)	VERY POORLY DRAINED (SEE NOTE 8)
PD	POORLY DRAINED (SEE NOTE 8)
	\ ·· <del>-</del> /



# EXISTING CONDITIONS PLAN

D.R. LEMIEUX BUILDERS, LLC
OF


TAX MAP U4, LOT 69 242 SOUTH MAIN STREET NEWMARKET, NEW HAMPSHIRE


1	05/22/23	ADD PRIME WETLANDS & SOILS	M.T.L.
NO.	DATE	DESCRIPTION	BY


DRAWN BY:	W.D.C.	DATE: OCTOBER 10, 2022
CHECKED BY:	B.T.	DRAWING NO. 7630B
JOB NO.	7630	SHEET 2 OF 2





Serving Your Professional Surveying & Mapping Needs 102 Kent Place, Newmarket, NH 03857 (603) 659-6560 Offices in Bedford & Keene, NH and Kennebunk, ME http://www.doucetsurvey.com


















PARKING STALL FOR THE PHYSICALLY CHALLENGED

NOT TO SCALE




VERT. GRANITE CURB/BIT. SIDEWALK DETAIL


NOT TO SCALE

NOTE: GRAVEL SPECIFICATIONS FOR SIDEWALK

ARE THE SAME FOR THE GRAVEL ACCESS PATHS.



1:10 MAX. SLOPE 36" A.D.A. MIN. 1:10 MAX. SLOPE (PROVIDE PLATFORM FULL WIDTH OF HC PARKING STALLS)
SEE SITE PLAN SHEETS
SIDEWALK RAMP DETAIL
NOT TO SCALE



RECTANGULAR RAPID
FLASHING BEACON (RRFB) DETAIL


TRAFFIC CC				ONTRO	OL S	SCH	IEDULE
SIGN NUMBER	SIGN	SIZE C	F SIGN HEIGHT	DESCRIPTION	MOUNT TYPE	MOUNT HEIGHT	REMARKS
R1-1	STOP	30"	30"	WHITE ON RED	CHANNEL	7'-0"	REFLECTORIZED SIGN
41-0342		30"	30"	BLACK ON YELLOW	CHANNEL	8'-6"	REFLECTORIZED SIGN
R7-8	HANDICAPPED PARKING	12"	18"	BLUE & GREEN ON WHITE	CHANNEL	7'-0"	REFLECTORIZED SIGN

PREPARED FOR:

DR LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857




70 PORTSMOUTH AVE, THIRD FLOOR, SUITE 2 STRATHAM, N.H. 03885 PHONE: 603-583-4860, FAX. 603-583-4863



STREET SIGN DETAIL


STOP SIGN (R1-1) 30" × 30"



NOTE: IN AREAS OF ROCK EXCAVATION, MINIMUM 9" BANK RUN GRAVEL SHALL BE PLACED

TYPICAL PAVEMENT SECTION


NEW ASPHALT - NTS



 PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL CONFORM TO STREET OPENING REGULATIONS.
 NEW ROADWAY CONSTRUCTION SHALL CONFORM TO SUBDIVISION SPEC'S. BACKFILL MATERIALS SHALL BE SCREENED GRAVEL WITH

NO STONES LARGER THAN 6".

TYPICAL DRAINAGE TRENCH DETAIL




REVISIONS:	DATE:

# CONSTRUCTION DETAILS D1

RESIDENTIAL DEVELOPMENT
TAX MAP U4, LOT 69
242 SOUTH MAIN STREET
NEWMARKET, NEW HAMPSHIRE

DATE:	MAY 2023	SCALE:	NTS
PROJ. N0:	NH-1449	SHEET NO.	7



### PIPE DUTLET PROTECTION


TABLE 7-24-RECOMMENDED	RIP RAP GRA	DATION RANGES
d50 SIZE= 0.25	FEET	3 INCHES
% OF WEIGHT SMALLER THAN THE GIVEN d50 SIZE		STONE(INCHES) TO
100%	5	6
85%	4	5
50%	3	5
15%	1	2

PREPARED FOR:

DR LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857



70 PORTSMOUTH AVE, THIRD FLOOR, SUITE 2 STRATHAM, N.H. 03885 PHONE: 603-583-4860 FAX. 603-583-4863



ROADWAY BACKFILL

SHALL CONFORM 1

STANDARD SPEC'S

ASTM C33/C33M #67

UNDISTURBED

4 4

MUNICIPAL SPEC'S.

1 DEBRIS; 2 PAVEMENT PIECES;

4 TOP SOIL; 5 WET OR SOFT MUCK;

6 PEAT OR CLAY; 7 EXCAVATED LEDGE;

**←** 3'−0" MIN. −−−

OR D + 2'(WHICHEVER IS GREATER)

ASTM D2412-02 DURING MANUFACTURE

STANDARD BACKFILL SPEC'S. (Env-Wq 704.11(h))
-NATURAL MATERIALS EXCAVATED FROM THE TRENCH
DURING CONSTRUCTION EXCLUDING:

8 ROCKS >6" IN LARGEST DIMENSION; 9 ANY MATERIAL NOT APPROVED BY THE ENGINEER

TYPICAL SEWER TRENCH DETAIL

MATCH EXISTING PAVEMENT DEPTHS.

1. PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL

2. NEW ROADWAY CONSTRUCTION SHALL CONFORM TO

12" SAND BLANKET, MATERIA

SHALL BE GRADED SAND, FREE FROM ORGANIC MATERIALS. GRADATION — 100% PASSING A

1/2" SEIVE, AND A MAX. 15%

PASSING THE #200 SEIVE.

CRUSHED STONE BEDDING
FOR FULL WIDTH OF THE PIPE


6" BELOW PIPE IN EARTH

12" BELOW PIPE IN LEDGE

ROCK

3. PLASTIC SEWER PIPE SHALL HAVE A PIPE STIFFNESS RATING OF AT LEAST 46 POUNDS PER SQUARE INCH AT 5 PERCENT PIPE

DIAMETER DEFLECTION, AS MEASURED IN ACCORDANCE WITH



REVISIONS PER REVIEW COMMENTS	8-16-23
REVISIONS:	DATE:

STAINLESS STEEL

PIPE SECTION

- FLEXIBLE WATER TIGHT

EXISTING

· CONCRETE

MANHOLE

PROOFING CLAMP; COAT WITH


WATERPROOF ASPHALT SEALANT

PIPE-TO-STRUCTURE CONNECTION.

# CONSTRUCTION DETAILS D1


RESIDENTIAL DEVELOPMENT TAX MAP U4, LOT 69 242 SOUTH MAIN STREET NEWMARKET, NEW HAMPSHIRE

DATE:	MAY 2023	SCALE:	NTS
PROJ. N0:	NH-1449	SHEET NO.	8



### - ONE STANDARD FULL LENGTH OF WATER MAIN TO BE CENTERED OVER SEWER WATER MAIN -SEWERS CROSSING WATER MAINS SHALL BE LAID TO PROVIDE A MINIMUM VERTICAL DISTANCE OF 18 INCHES (460 MM) BETWEEN THE OUTSIDE OF THE WATER MAIN AND THE OUTSIDE OF THE SEWER. THÍS SHALL BE THE CASE WHERE THE WATER MAIN IS ABOVE THE SEWER. THE CROSSING SHALL BE ARRANGED SO THAT THE SEWER - SELECT BACKFILL COMPACTED JOINTS WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE WATER MAIN IN 6" LAYERS - 95% STANDARD PROCTOR DENSITY WHEN IT IS IMPOSSIBLE TO OBTAIN PROPER HORIZONTAL AND VERTICAL SEPARATION AS STIPULATED ABOVE, ONE OF THE FOLLOWING METHODS MUST BE SPECIFIED: WATER MAINS AND SERVICES CROSSING SEWERS A. THE SEWER SHALL BE DESIGNED AND CONSTRUCTED EQUAL TO WATER PIPE, AND AND SERVICES SHALL BE LAID TO PROVIDE A MINIMUM SHALL BE PRESSURE TESTED AT 150 PSI (1034 KPA) TO ASSURE WATERTIGHTNESS. VERTICAL DISTANCE OF 18 INCHES B. EITHER THE WATER MAIN OR THE SEWER LINE MAY BE ENCASED IN A WATERTIGHT BETWEEN PIPES. WATER MAIN JOINTS CARRIER PIPE WHICH EXTENDS 10 FEET (3 M) ON BOTH SIDES OF THE CROSSING, WILL BE EQUIDISTANT AND AS FAR AS POSSIBLE FROM THE SEWER JOINTS MEASURED PERPENDICULAR TO THE WATER MAIN. THE CARRIER PIPE SHALL BE OF MATERIALS APPROVED BY THE REGULATORY AGENCY FOR USE IN WATER MAIN CONSTRUCTION. WATER MAIN ABOVE SEWER

## TYPICAL WATER/SEWER SEPERATION DETAILS NOT TO SCALE





TYPICAL TRENCH DETAIL

FOR WATER SYSTEM

STEEL INSERTS ON THE PE SERVICE LINE TUBING TYPICAL WATER SERVICE CONNECTION


NOTE: ALL COMPRESSION FITTINGS USE STAINLESS






SOILS BEARING CAPACIT

SOIL





# THRUST BLOCK LOCATIONS

TYPICAL THRUST BLOCK DETAILS

NOT TO SCALE


THE FOLLOWING PRECAUTIONS MUST BE OBSERVED WHEN CONSTRUCTING BLOCKS:

- 1. BLOCKS MUST BE POURED AGAINST UNDISTURBED SOIL.
- 2. PIPE JOINTS AND BOLTS MUST BE ACCESSIBLE.
- CONCRETE SHOULD BE CURED AT LEAST 5 DAYS AND SHALL HAVE A COMPRESSIVE STRENGTH OF 2000 PSI AT 28 DAYS.
- 4. BLOCKS MUST BE POSITIONED TO COUNTERACT THE DIRECTION OF THE RESULTANT THRUST FORCE.


RESTRAINED PUSH—ON AND MECHANICAL JOINTS ARE AVAILABLE FOR ALL PIPE SIZES AND PRESENT NO INSTALLATION PROBLEMS. THEY ARE USED FOR RESISITING THRUST FORCES WHERE THERE IS NO SPACE OR WHERE SOIL BEHIND THE FITTING WILL NOT PROVIDE ADEQUATE SUPPORT. THIS RESTRAINING METHOD INVOLVES THE PLACEMENT OF THESE SPECIAL JOINTS AT APPROPRIATE FITTINGS AND FOR A PREDETERMINED NUMBER OF PIPE LENGTHS ON EACH SIDE. TIE RODS MAY BE USED BY THEMSELVES OR IN COMBINATION WITH OTHER RESTRAINT DEVICES. WHEN TIE RODS ARE USED WITH STEEL BANDS AROUND THE PIPE BARREL, ONLY ONE(1) ROD SHALL BE ATTACHED TO EACH BAND AND THE BAND SHALL BE COCKED TO PREVENT SLIPPAGE ALONG THE PIPE BARREL. A BAND PLACED BEHIND A BELL MAY BE USED WITH TWO(2) RODS. FOR MECHANICAL JOINT PIPE, TIE RODS MAY BE THREADED THROUGH THE BOLT HOLES IN A FLANGE AND SECURED BY NUTS. ALL RODS SHALL BE MADE OF OR COATED WITH CORROSION RESISTANT MATERIALS TO PREVENT RUST AND DETERIORATION.

RESTRAINT MAY BE NECESSARY FOR MORE THAN ONE (1) PIPE LENGTH ON EACH SIDE OF ANY CHANGE IN DIRECTION,

DEADEND OR TEE.



HIGH PRESSURE HYDRANTS SHALL BE RED WITH YELLOW CAPS. HYDRANT INSTALLATION DETAIL



RESULTANT THRUST AT FITTINGS @ 100 PSI (TOTAL POUNDS)					
NOM. PIPE DIA. (IN.)	DEAD END	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND
4	1810	2559	1385	706	355
6	3739	5288	2862	1459	733
8	6433	9097	4923	2510	1261
10	9677	13685	7406	3776	1897
12	13685	19353	10474	5340	2683
14	18383	26001	14072	7174	3604
16	23779	33628	18199	9278	4661
18	29865	42235	22858	11653	5855
20	35644	51822	28046	14298	7183
24	52279	73934	40013	20398	10249
30	80425	113738	61554	31380	15766
36	115209	162931	88177	44952	22585
42	155528	219950	119036	60684	30489
48	202683	286637	155127	79083	39733
54	256072	362140	195989	99914	50109

NOTE: TO DETERMINE THRUST AT PRESSURES OTHER THAN 100 PSI, MULTIPLY THE THRUST OBTAINED IN THE TABLE BY THE RATIO OF THE PRESSURE TO 100. FOR EXAMPLE: THE THRUST ON A 12", 90° BEND @ 125 PSI IS:  $19353 \times 125/100 = 24191 LBS.$ 

TO DETERMINE THE SIZE OF A CONCRETE THRUST BLOCK, DIVIDE THE TOTAL FORCE BY THE BEARING VALUE OF THE CONSTITUENT SOIL. THE QUOTIENT WILL BE THE SIZE OF THE BEARING OF THE THRUST BLOCK IN SQUARE FEET. APPROXIMATE VALUES FOR VARIOUS TYPES OF SOIL ARE LISTED BELOW. NO RESPONSIBILITY CAN BE ASSUMED FOR THE ACCURACY OF THE DATA REPRESENTED DUE TO THE WIDE VARIATION OF BEARING VALUES FOR EACH SOIL TYPE.


### NOTE: ALL UTILITIES SHALL BE REVIEWED AND APPROVED BY APPROPRIATE UTILITY COMPANY. SERVICE BOX CONNECTIONS SHALL BE "FLUSH MOUNT" TO GREATEST EXTENT POSSIBLE AND LOCATED AT PROPERTY LINE CORNERS. PLASTIC MARKER TAPE 12" MIN. ABOVE CABLES PERMEABLE SAND (1" O MAX) 4" ELECTRIC SERVICE CABLES 250 VAC OR LESS 3" CATV CABLE BURIAL UNLESS UNDER (PVC-SCH 40) ROADWAY) PVC-SCH 40 **(** TELEPHONE PRIMARY POWER CABLE -(DIRECT BURIAL UNLESS UNDER ROADWAY AND AS LOCATED IN DWGS, 4" SCH-40 PVC) 7,200 VAC. OTHER POWER, TELEPHONE CATV, ETC., CABLES ARE NO CLOSER THAN 12".

PREPARED FOR:

DR LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857



70 PORTSMOUTH AVE, THIRD FLOOR, SUITE 2 STRATHAM, N.H. 03885 PHONE: 603-583-4860 FAX. 603-583-4863



### DETAIL OF SEWER SERVICE

- 1) SEWER SERVICE FROM PROPERTY LINE TO 10' OUTSIDE OF BUILDING SHALL BE INSTALLED UNDER THIS CONTRACT ONLY WHEN OUTSIDE THE
- TRENCH DEWATERING OR LEDGE EXCAVATION IS REQUIRED. 2) PIPE DEPTH AT HOUSE SHALL BE ABOVE THE SEASONAL GROUND WATER LEVEL.

LOAM AREA PAVED AREA

—— 3'−0" MIN. ——<del>-</del>

1. PAVEMENT REPAIR IN EXISTING ROADWAYS SHALL CONFORM TO STREET OPENING REGULATIONS. 2. NEW ROADWAY CONSTRUCTION SHALL CONFORM TO

TYPICAL SEWER TRENCH DETAIL

NOT TO SCALE

OR D + 2'(WHICHEVER IS GREATER)

SUBDIVISION SPEC'S.

SEE NOTES 1 & 2

\_ ROADWAY BACKFILL

SHALL CONFORM TO STANDARD SPEC'S

12" PROTECTIVE SAND BLANKET

COMPACTED AS SPECIFIED

CRUSHED STONE OR

SCREENED GRAVEL BEDDING

6" BELOW PIPE IN EARTH

12" BELOW PIPE IN LEDGE

FOR FULL WIDTH OF THE PIPE

4" CRUSHED GRAVEL

18" BANK-RUN GRAVEL

4" COMPACTED LOAM \_\_


UNDISTURBED

& SEEDED

METAL IMPREGNATED
MARKING TAPE (TO AID
IN THE LOCATING OF BURIED


PIPE WITH METAL
DETECTING EQUIPMENT)
(SEE NOTE #12)

- 3) SEWER SHALL BE BELOW SLAB ONLY WHEN BASEMENT TOILETS EXIST. 4) JOINTS SHALL BE DEPENDENT UPON A NEOPRENE OR ELASTOMERIC GASKET FOR WATER TIGHTNESS. ALL JOINTS SHALL BE PROPERLY MATCHED WITH THE PIPE MATERIALS USED. WHERE DIFFERING MATERIALS ARE TO BE CONNECTED, AST AT
- THE STREET SEWER WYE OR, AT THE FOUNDATION WALL, APPROPRIATE MANUFACTURED ADAPTERS SHALL BE USED 5) WYES: WHERE WYE IS NOT AVAILABLE IN THE EXISTING STREET SEWER, AN APPROPRIATE CONNECTION SHALL BE MADE FOLLOWING
- MANUFACTURERS INSTRUCTIONS USING A BOLTED, CLAMPED, OR EPOXY-CEMENTED SADDLE, TAPPED INTO A SMOOTHLY DRILLED OR SAWN OPENING IN THE SEWER.



STONE DRIP EDGE SECTION


NOT TO SCALE




# CONSTRUCTION DETAILS D2

RESIDENTIAL DEVELOPMENT TAX MAP U4, LOT 69 242 SOUTH MAIN STREET NEWMARKET, NEW HAMPSHIRE

DATE:	MAY 2023	SCALE:	NTS
PROJ. N0:	NH-1449	SHEET NO.	10



UTILITY TRENCH DETAIL



1. STONE FOR A STABILIZED CONSTRUCTION ENTRANCE SHALL BE 3 INCH STONE, RECLAIMED STONE, OR RECYCLED CONCRETE EQUIVALENT.

2. THE LENGTH OF THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 50 FEET, EXCEPT FOR A SINGLE RESIDENTIAL LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY. 3. THE THICKNESS OF THE STONE FOR THE STABILIZED ENTRANCE SHALL NOT BE LESS THAN 6 INCHES. 4. THE WIDTH OF THE ENTRANCE SHALL NOT BE LESS THAN THE FULL WIDTH OF THE ENTRANCE WHERE INGRESS OR EGRESS OCCURS OR 10 FEET. WHICH EVER IS GREATER. 5. GEOTEXTILE FILTER CLOTH SHALL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING THE STONE. FILTER CLOTH IS NOT REQUIRED FOR A SINGLE FAMILY RESIDENCE LOT. 6. ALL SURFACE WATER THAT IS FLOWING TO OR DIVERTED TOWARD THE CONSTRUCTION ENTRANCE SHALL

BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A BERM WITH 5:1 SLOPES THAT CAN BE CROSSED BY VEHICLES MAY BE SUBSTITUTED FOR THE PIPE. 7. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION THAT WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL

STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEAN OUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, WASHED, OR TRACKED ONTO PUBLIC RIGHT-OF-WAY MUST BE REMOVED PROMPTLY

### STABILIZED CONSTRUCTION ENTRANCE

### TEMPORARY EROSION CONTROL MEASURES

1. THE SMALLEST PRACTICAL AREA SHALL BE DISTURBED DURING CONSTRUCTION, BUT NO MORE THAN 5 ACRES OF LAND SHALL BE EXPOSED BEFORE DISTURBED AREAS ARE STABILIZED\*. LIMIT EXPOSURE OF UNSTABILIZED SOIL TO 45-DAYS OR LESS. - PERIMETER CONTROLS MUST BE INSTALLED PRIOR TO EARTH MOVING OPERATIONS

STORMWATER PONDS, INFILTRATION BASINS AND SWALES MUST BE INSTALLED BEFORE ROUGH GRADING THE SITE.

RUNOFF MUST BE DIRECTED TO TEMPORARY PRACTICES UNTIL STORMWATER BMPS ARE STABILIZED

STORMWATER PONDS, INFILTRATION BASINS AND SWALES MUST BE STABILIZED PRIOR TO DIRECTING RUNOFF TO THEM. - EROSION CONTROL PRACTICES ARE TO BE INSPECTED WEEKLY AND AFTER 0.5; OF RAINFALL.

- CUT AND FILL SLOPES MUST BE STABILIZED WITHIN 72 HOURS OF ACHIEVING FINISHED GRADE

- roadways and parking areas must be stabilized within 72 hours of achieving finished grade.

2. EROSION, SEDIMENT AND DETENTION MEASURES SHALL BE INSTALLED AS SHOWN ON THE PLANS AND AT LOCATIONS AS REQUIRED OR DIRECTED BY THE ENGINEER ALL DISTURBED AREAS SHALL BE RETURNED TO ORIGINAL GRADES AND ELEVATIONS. 3. DISTURBED AREAS SHALL BE LOAMED WITH A MINIMUM OF 4" OF LOAM AND SEEDED WITH NOT LESS THAN 1.10 POUNDS OF

SEED PER 1000 SQUARE FEET OF AREA. (48 POUNDS PER ACRE) SEE SEED SPECIFICATIONS THIS SHEET 4. SILT FENCES AND OTHER EROSION CONTROLS SHALL BE INSPECTED WEEKLY AND AFTER EVERY RAIN EVENT GREATER THAN 0.5" DURING THE LIFE OF THE PROJECT. ALL DAMAGED AREAS SHALL BE REPAIRED, SEDIMENT DEPOSITS SHALL PERIODICALLY

5. AFTER ALL DISTURBED AREAS HAVE BEEN STABILIZED, THE TEMPORARY EROSION CONTROL MEASURES ARE TO BE REMOVED AND THE AREA DISTURBED BY THE REMOVAL SMOOTHED AND RE-VEGETATED.

6. AREAS MUST BE SEEDED AND MULCHED WITHIN 3 DAYS OF FINAL GRADING, PERMANENTLY STABILIZED WITHIN 15 DAYS OF FINAL GRADING, OR TEMPORARILY STABILIZED WITHIN 30 DAYS OF INITIAL DISTURBANCE OF SOIL.

\* AN AREA SHALL BE CONSIDERED STABLE IF ONE OF THE FOLLOWING HAS OCCURRED: - IN AREAS TO BE PAVED, BASE COURSE GRAVELS MEETING THE REQUIREMENTS OF NHDOT STANDARD FOR ROAD AND BRIDGE

CONSTRUCTION, 2016, ITEM 304.2 HAVE BEEN INSTALLED.

- A MINIMUM OF 85% VEGETATED GROWTH HAS BEEN ESTABLISHED.

- A MINIMUM OF 3 INCHES OF NON-EROSIVE MATERIAL SUCH AS RIPRAP HAS BEEN INSTALLED. - EROSION CONTROL BLANKETS HAVE BEEN PROPERLY INSTALLED.

### CONSTRUCTION SPECIFICATIONS

1. STRUCTURES SHALL BE INSTALLED ACCORDING TO THE DIMENSIONS SHOWN ON THE PLANS AT THE APPROPRIATE SPACING.

2. CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN SUCH A MANNER SO THAT EROSION AND AIR AND WATER POLLUTION WILL BE MINIMIZED.

3. WHEN TIMBER STRUCTURES ARE USED, THE TIMBER SHALL EXTEND AT LEAST 18" INTO THE SOIL.

4. STRAW BALES SHALL BE ANCHORED INTO THE SOIL USING 2" X 2" STAKES DRIVEN THROUGH THE BALES AND AT LEAST 18 INCHES IN TO THE SOIL. 5. SEEDING, FERTILIZING, AND MULCHING SHALL CONFORM TO THE RECOMMENDATIONS IN THE APPROPRIATED

VEGETATIVE BMP. 6. STRUCTURES SHALL BE REMOVED FROM THE CHANNEL WHEN THEIR USEFUL LIFE HAS BEEN COMPLETED. 7. THROUGHOUT THE DURATION OF CONSTRUCTION ACTIVITIES THE CONTRACTOR SHALL TAKE PRECAUTIONS AND INSTRUCTIONS FROM THE PLANNING DEPARTMENT IN ORDER TO PREVENT, ABATE AND CONTROL THE EMISSION OF FUGITIVE DUST INCLUDING BUT NOT LIMITED TO WETTING, COVERING, SHIELDING, OR VACUUMING.

8. THE NH COMMISSIONER OF AGRICULTURE PROHIBITS THE COLLECTION, POSSESSION, IMPORTATION, TRANSPORTATION, SALE, PROPAGATION, TRANSPLANTATION, OR CULTIVATION OF PLANTS BANNED BY NH LAW RSA 430:53 AND NH CODE ADMINISTRATIVE RULES AGR 3800. THE PROJECT SHALL MEET ALL REQUIREMENTS AND THE INTENT OF . RSA 430:53 AND AGR 3800 RELATIVE TO INVASIVE SPECIES

9. IN THE EVENT THAT GREATER THAN ONE ACRE OF CONTIGUOUS DISTURBANCE OCCURS, THE CONSTRUCTION SITE OPERATOR AND OWNER SHALL SUBMIT A NOTICE OF INTENT (NOI) TO USEPA, WASHINGTON, DC, STORMWATER NOTICE PROCESSING CENTER AT LEAST FOURTEEN DAYS PRIOR TO COMMENCEMENT OF WORK ON SITE. EPA WILL POST THE NOI AT

http://cfpubl.epa.gov/npdes/stormwater/noi/noisearch.cfm. AUTHORIZATION IS GRANTED UNDER THE PERMIT ONCE THE NOI IS SHOWN IN "ACTIVE STATUS".

# CONSTRUCTION SEQUENCE

DIRECTED TO THEM.

1. CUT AND REMOVE TREES IN CONSTRUCTION AREAS AS REQUIRED OR DIRECTED.

2. CONSTRUCT AND/OR INSTALL TEMPORARY AND PERMANENT SEDIMENT EROSION AND DETENTION CONTROL FACILITIES AS REQUIRED. EROSION, SEDIMENT AND DETENTION CONTROL FACILITIES SHALL BE INSTALLED AND STABILIZED PRIOR TO ANY EARTH MOVING OPERATION AND PRIOR TO DIRECTING RUNOFF TO THEM.

3. CLEAR, CUT, GRUB AND DISPOSE OF DEBRIS IN APPROVED FACILITIES. STUMPS AND DEBRIS ARE TO BE REMOVED FROM SITE AND DISPOSED OF PER STATE AND LOCAL REGULATIONS.

4. EXCAVATE AND STOCKPILE TOPSOIL /LOAM. ALL AREAS SHALL BE STABILIZED IMMEDIATELY AFTER GRADING. 5. CONSTRUCT TEMPORARY CULVERTS AS REQUIRED OR DIRECTED.


6. CONSTRUCT THE ROADWAY AND ITS ASSOCIATED DRAINAGE STRUCTURES. ALL ROADWAYS, AND CUT/FILL SLOPES SHALL BE STABILIZED AND/OR LOAMED AND SEEDED WITHIN 72-HOURS OF ACHIEVING FINISH GRADE AS APPLICABLE. 7. INSTALL PIPE AND CONSTRUCTION ASSOCIATED APPURTENANCES AS REQUIRED OR DIRECTED. ALL DISTURBED AREAS SHALL STABILIZED IMMEDIATELY AFTER GRADING. 8. BEGIN PERMANENT AND TEMPORARY SEEDING AND MULCHING. ALL CUT AND FILL SLOPES AND DISTURBED AREAS

SHALL BE SEEDED OR MULCHED AS REQUIRED, OR DIRECTED. 9. DAILY OR AS REQUIRED, CONSTRUCT TEMPORARY BERMS, DRAINAGE CHECK DAMS, DITCHES, SEDIMENT TRAPS, ETC. TO PREVENT EROSION ON THE SITE AND PREVENT ANY SILTATION OF ABUTTING WATERS OR PROPERTY.

10. INSPECT AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL MEASURES DURING CONSTRUCTION 11. COMPLETE PERMANENT SEEDING AND LANDSCAPING

12. REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER SEEDING AREAS HAVE ESTABLISHED THEMSELVES AND SITE IMPROVEMENTS ARE COMPLETE. SMOOTH AND REVEGETATE ALL DISTURBED AREAS. 13. ALL SWALES AND DRAINAGE STRUCTURES WILL BE CONSTRUCTED AND STABILIZED PRIOR TO HAVING RUNOFF

14. FINISH PAVING ALL ROADWAYS. 15. LOT DISTURBANCE OTHER THAN THAT SHOWN ON THE APPROVED PLANS SHALL NOT COMMENCE UNTIL THE ROADWAY HAS THE CRUSHED STONE COURSE TO DESIGN ELEVATION/REQUIRED COMPACTION AND THE ASSOCIATED DRAINAGE IS COMPLETE AND STABLE.



### WINTER MAINTENANCE

1. ALL DISTURBED AREAS THAT DO NOT HAVE AT LEAST 85% VEGETATIVE COVERAGE PRIOR TO OCTOBER 15TH, SHALL BE STABILIZED BY APPLYING MULCH AT A RATE OF 3-4 TONS PER ACRE. ALL SIDE SLOPES, STEEPER THAN 4:1, THAT ARE NOT DIRECTED TO SWALES OR DETENTION BASINS, SHALL BE LINED WITH BIODEGRADABLE/PHOTODEGRADABLE "JUTE MATTING" (EXCELSIOR'S CURLEX II OR EQUAL). ALL OTHER SLOPES SHALL BE MULCHED AND TACKED AT A RATE OF 3-4 TONS PER ACRE. THE APPLICATION OF MULCH AND/OR JUTE MATTING SHALL NOT OCCUR OVER EXISTING SNOW COVER. IF THE SITE IS ACTIVE AFTER NOVEMBER 15TH, ANY SNOW THAT ACCUMULATES ON DISTURBED AREAS SHALL BE REMOVED. PRIOR TO SPRING THAW ALL AREAS WILL BE STABILIZED, AS DIRECTED ABOVE.

2. ALL SWALES THAT DO NOT HAVE FULLY ESTABLISHED VEGETATION SHALL BE EITHER LINED WITH TEMPORARY JUTE MATTING OR TEMPORARY STONE CHECK DAMS (APPROPRIATELY SPACED). STONE CHECK DAMS WILL BE MAINTAINED THROUGHOUT THE WINTER MONTHS. IF THE SWALES ARE TO BE MATTED WITH PERMANENT LINERS OR RIPRAP WITH ENGINEERING FABRIC, THIS SHALL BE COMPLETED PRIOR TO WINTER SHUTDOWN OR AS SOON AS THEY ARE PROPERLY GRADED AND SHAPED

3. PRIOR TO OCT. 15TH ALL ROADWAY AND PARKING AREAS SHALL BE BROUGHT UP TO AND THROUGH THE BANK RUN GRAVEL APPLICATION. IF THESE AREAS' ELEVATIONS ARE PROPOSED TO REMAIN BELOW THE PROPOSED SUBGRADE ELEVATION, THE SUBGRADE MATERIAL SHALL BE ROUGHLY CROWNED AND A 3" LAYER OF CRUSHED GRAVEL SHALL BE PLACED AND COMPACTED. THIS WILL ALLOW THE SUBGRADE TO SHED RUNOFF AND WILL REDUCE ROADWAY EROSION. THIS CRUSHED GRAVEL DOES NOT HAVE TO CONFORM TO NH DOT 304.3, BUT SHALL HAVE BETWEEN 15-25% PASSING THE #200 SIEVE AND THE LARGEST STONE SIZE SHALL BE 2". IF THE SITE IS ACTIVE AFTER NOVEMBER 15TH, ANY ACCUMULATED SNOW SHALL BE REMOVED FROM ALL ROADWAY AND PARKING AREAS.

4. AFTER OCTOBER 15TH, THE END OF NEW HAMPSHIRE'S AVERAGE GROWING SEASON, NO ADDITIONAL LOAM SHALL BE SPREAD ON SIDE SLOPES AND SWALES. THE STOCKPILES THAT WILL BE LEFT UNDISTURBED UNTIL SPRING SHALL BE SEEDED BY THIS DATE. AFTER OCTOBER 15TH, ANY NEW OR DISTURBED PILES SHALL BE MULCHED AT A RATE OF 3-4 TONS PER ACRE. ALL STOCKPILES THAT WILL REMAIN THROUGHOUT THE WINTER SHALL BE SURROUNDED WITH SILT

### SEEDING SPECIFICATIONS

1. GRADING AND SHAPING

2. SEEDBED PREPARATION

A. SLOPES SHALL NOT BE STEEPER THAN 2:1;3:1 SLOPES OR FLATTER ARE PREFERRED. WHERE MOWING WILL BE DONE, 3:1 SLOPES OR FLATTER ARE RECOMMENDED.

A. SURFACE AND SEEPAGE WATER SHOULD BE DRAINED OR DIVERTED FROM THE SITE TO PREVENT DROWNING OR WINTER KILLING OF THE PLANTS.

B. STONES LARGER THAN 4 INCHES AND TRASH SHOULD BE REMOVED BECAUSE THEY INTERFERE WITH SEEDING AND FUTURE MAINTENANCE OF THE AREA. WHERE FEASIBLE, THE SOIL SHOULD BE TILLED TO A DEPTH OF ABOUT 4 INCHES TO PREPARE A SEEDBED AND MIX FERTILIZER AND LIME INTO THE SOIL. THE SEEDBED SHOULD BE LEFT IN REASONABLY FIRM AND SMOOTH CONDITION. THE LAST TILLAGE OPERATION SHOULD BE PERFORMED ACROSS THE SLOPE WHEREVER PRACTICAL.

A. LIME AND FERTILIZER SHOULD BE APPLIED PRIOR TO OR AT THE TIME OF SEEDING AND INCORPORATED INTO THE SOIL KINDS AND AMOUNTS OF LIME AND FERTILIZER SHOULD BE BASED ON AN EVALUATION OF SOIL TESTS. WHEN A SOIL TEST IS NOT AVAILABLE, THE FOLLOWING MINIMUM AMOUNTS SHOULD BE APPLIED:

AGRICULTURAL LIMESTONE, 2 TONS PER ACRE OR 100 LBS PER 1,000 SQ. FT.. NITROGEN(N), 50 LBS PER ACRE OR 1. 1 LBS PER 1,000 SQ.FT.

PHOSPHATE(P205), 100 LBS PER ACRE OR 2. 2 LBS PER 1,000 SQ.FT.

POTASH(K20), 100 LBS PER ACRE OR 2. 2 LBS PER 1,000 SQ.FT.

(NOTE: THIS IS THE EQUIVALENT OF 500 LBS PER ACRE OF 10-20-20 FERTILIZER OR 1,000 LBS PER ACRE OF 5-10-10.)

. SEED SHOULD BE SPREAD UNIFORMLY BY THE METHOD MOST APPROPRIATE FOR THE SITE. METHODS INCLUDE BROADCASTING, DRILLING AND HYDROSEEDING. WHERE BROADCASTING IS USED, COVER SEED WITH .25 INCH OF SOIL OR LESS, BY CULTIPACKING OR RAKING.

C. REFER TO TABLE(G-E1 THIS SHEET) FOR APPROPRIATE SEED MIXTURES AND TABLE(H-E1 THIS SHEET) FOR RATES OF SEEDING. ALL LEGUMES (CROWN VETCH, BIRDS FOOT TREFOIL, AND FLAT PEA) MUST BE INOCULATED WITH THEIR SPECIFIC INOCULANT.

D. WHEN SEEDED AREAS ARE MULCHED, PLANTINGS MAY BE MADE FROM EARLY SPRING TO EARLY OCTOBER. WHEN SEEDED AREAS ARE NOT MULCHED, PLANTINGS SHOULD BE MADE FROM EARLY SPRING TO MAY 20 OR FROM AUGUST 10 TO SEPTEMBER 1.

4. MULCH

A. HAY, STRAW, OR OTHER MULCH, WHEN NEEDED, SHOULD BE APPLIED IMMEDIATELY AFTER SEEDING. B. MULCH WILL BE HELD IN PLACE USING APPROPRIATE TECHNIQUES FROM THE BEST MANAGEMENT PRACTICE FOR MULCHING. HAY OR STRAW MULCH SHALL BE PLACED AT A RATE OF 90 LBS PER 1000 SQ. FT.

5. MAINTENANCE TO ESTABLISH A STAND

BECOME ESTABLISHED.

A. PLANTED AREA SHOULD BE PROTECTED FROM DAMAGE BY FIRE, GRAZING, TRAFFIC, AND DENSE WEED GROWTH. B. FERTILIZATION NEEDS SHOULD BE DETERMINED BY ONSITE INSPECTIONS. SUPPLEMENTAL FERTILIZER IS USUALLY THE KEY TO FULLY COMPLETE THE ESTABLISHMENT OF THE STAND BECAUSE MOST PERENNIAL STAKE 2 TO 3 YEARS TO

C. IN WATERWAYS, CHANNELS, OR SWALES WHERE UNIFORM FLOW CONDITIONS ARE ANTICIPATED, OCCASIONAL


MOWING MAY BE NECESSARY TO CONTROL GROWTH OF WOODY VEGETATION.

PREPARED FOR:

DR LEMIEUX BUILDERS, INC. 76 EXETER ROAD NEWMARKET, NH 03857



70 PORTSMOUTH AVE, THIRD FLOOR, SUITE 2 STRATHAM, N.H. 03885 PHONE: 603-583-4860 FAX. 603-583-4863



CONSTRUCTION SPECIFICATIONS 1. WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES AND FILTER CLOTH SHALL BE FASTENED TO WOVEN WIRE EVERY 24" AT TOP MID AND BOTTOM SECTIONS AND BE EMBEDDED INTO GROUND A MINIMUM OF 8". 2. THE FENCE POSTS SHALL BE A MINIMUM 48" LONG, SPACED A MAXIMUM 10' APART, AND DRIVEN A MINIMUM OF 16" INTO THE GROUND. THERE SHALL BE NO PLASTIC, MULTI-FILAMENT OR MONOFILAMENT POLYPROPYLENE NETTING OR MESH WITH AN OPENING SIZE GREATER THAN !" 3. WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER, THE ENDS OF THE FABRIC

SHALL BE OVERLAPPED BY SIX INCHES, FOLDED AND STAPLED TO PREVENT SEDIMENT FROM BY-PASSING. 4. MAINTENANCE SHALL BE PERFORMED AS NEEDED AND SEDIMENT REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE AND PROPERLY DISPOSED OF.

5. PLACE THE ENDS OF THE SILT FENCE UP CONTOUR TO PROVIDE FOR SEDIMENT STORAGE. 6. SILT FENCES SHALL BE REMOVED WHEN NO LONGER NEEDED AND THE SEDIMENT COLLECTED SHALL BE DISPOSED AS DIRECTED BY THE ENGINEER. THE AREA DISTURBED BY THE REMOVAL SHALL BE SMOOTHED AND RE-VEGETATED

MAINTENANCE

2' MIN.

HEIGHT

COVER

1. SILT FENCES SHALL BE INSPECTED IMMEDIATELY AFTER EACH RAINFALL AND AT LEAST DAILY DURING PROLONGED RAINFALL. ANY REPAIRS THAT ARE REQUIRED SHALL BE MADE

2. IF THE FABRIC ON A SILT FENCE SHOULD DECOMPOSE OR BECOME INEFFECTIVE DURING THE EXPECTED LIFE OF THE FENCE, THE FABRIC SHALL BE REPLACED PROMPTLY. 3. SEDIMENT DEPOSITS SHOULD BE INSPECTED AFTER EVERY STORM EVENT. THE DEPOSITS SHOULD BE REMOVED WHEN THEY REACH APPROXIMATELY ONE HALF THE HEIGHT OF THE

4. SEDIMENT DEPOSITS THAT ARE REMOVED OR LEFT IN PLACE AFTER THE FABRIC HAS BEEN REMOVED SHALL BE GRADED TO CONFORM WITH THE EXISTING TOPOGRAPHY AND VEGETATED.

### SEEDING GUIDE

USE	SEEDING MIXTURE 1/	DROUGHTY	WELL DRAINED	MODERATELY WELL DRAINED	POORLY DRAINED
STEEP CUTS AND FILLS, BORROW AND DISPOSAL	A B C	FAIR POOR POOR	GOOD GOOD GOOD	GOOD FAIR EXCELLENT	FAIR FAIR GOOD
AREAS	D E	FAIR FAIR	FAIR EXCELLENT	GOOD EXCELLENT	EXCELLENT POOR
WATERWAYS, EMERGENCY SPILLWAYS, AND OTHER CHANNELS WITH FLOWING WATER.	A C D	GOOD GOOD GOOD	GOOD EXCELLENT EXCELLENT	GOOD EXCELLENT EXCELLENT	FAIR FAIR FAIR
LIGHTLY USED PARKING LOTS, ODD AREAS, UNUSED LANDS, AND LOW INTENSITY USE RECREATION SITES.	A B C D	GOOD GOOD GOOD FAIR	GOOD GOOD EXCELLENT GOOD	GOOD FAIR EXCELLENT GOOD	FAIR POOR <u>FAIR</u> EXCELLENT
PLAY AREAS AND ATHLETIC FIELDS. (TOPSOIL IS ESSENTIAL FOR GOOD TURF.)	F G	FAIR FAIR	EXCELLENT EXCELLENT	EXCELLENT EXCELLENT	<u>2/</u> <u>2/</u>

GRAVEL PIT, SEE NH-PM-24 IN APPENDIX FOR RECOMMENDATION REGARDING RECLAMATION OF SAND AND GRAVEL PITS.

/ REFER TO SEEDING MIXTURES AND RATES IN TABLE 7-36. POORLY DRAINED SOILS ARE NOT DESIRABLE FOR USE AS PLAYING AREA AND ATHLETIC FIELDS. NOTE: TEMPORARY SEED MIX FOR STABILIZATION OF TURF

SHALL BE WINTER RYE OR DATS AT A RATE OF 2.5 LBS. PER 1000 S.F. AND SHALL BE PLACED PRIOR TO DCT. 15. IF PERMANENT SEEDING NOT YET COMPLETE.

Mix material should consist of 30-50% large (1-3") particles. The organic matter content should be 25%-65%, dry weight basis. The organic matter may originate from a variety of vegetative sources, but needs to be fibrous and elongated. The mix shall be free of silt clay, fine sand, refuse and contaminants or any material toxic to plant growth. Erosion Control Mix berms are effective filters for overland flow conditions and should not be used to filter concentrated flow such as that found in drainage ditchs, streams, etc.

### Erosion Control Mix Berm

	SEEDING	RATES	
	MIXTURE_	POUNDS PER ACRE	POUNDS PER 1,000 Sq. Ft.
	A. TALL FESCUE CREEPING RED FESCUE RED TOP TOTAL	20 20 <u>2</u> 42	0.45 0.45 <u>0.05</u> 0.95
	B. TALL FESCUE CREEPING RED FESCUE CROWN VETCH OR	15 10 15	0.35 0.25 0.35
	FLAT PEA TOTAL	30 40 OR 55	0.75 0.95 OR 1.35
*	C. TALL FESCUE CREEPING RED FESCUE BIRDS FOOT TREFOIL TOTAL	20 20 <u>8</u> 48	0.45 0.45 <u>0.20</u> 1.10
	D. TALL FESCUE FLAT PEA TOTAL	20 <u>30</u> 50	0.45 <u>0.75</u> 1.20
	E. CREEPING RED FESCUE <u>1/</u> KENTUCKY BLUEGRASS <u>1/</u> TOTAL	50 <u>50</u> 100	1.15 1.15 2.30
	F. TALL FESCUE 1	150	3.60
	1/ FOR HEAVY USE ATHLETIC FIE NEW HAMPSHIRE COOPERATIVE EX CURRENT VARIETIES AND SEEDING	TENSION TURF S	

**REVISIONS:** DATE:

# EROSION & SEDIMENTATION

RESIDENTIAL DEVELOPMENT TAX MAP U4, LOT 69 242 SOUTH MAIN STREET NEWMARKET, NEW HAMPSHIRE


DATE:	MAY 2023	SCALE:	NTS
PROJ. N0:	NH-1449	SHEET NO.	11

### Landscape Notes

- 1. Design is based on drawings by Beals Associates, PLLC. Drawings may require adjustment due to actual field conditions.
- 2. The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from
- 3. Erosion Control shall be in place prior to construction.
- 4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water bodies, Wetlands and/or drainage ways prior to any construction.
- 5. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies or changes in layout and/or grade relationships prior to construction.
- 6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- 7. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line or at the distance in feet from the trunk equal to the diameter of the tree caliper in inches, whichever is greater, and shall be expanded to include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- 8. This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request.
- 9. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor.
- 10. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 811 or 888-DIG-SAFE (1-888-344-7233.)
- 11. The Contractor shall procure any required permits prior to construction.
- 12. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
- 13. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a Contractor is aware of a potential issue and does not bring it to the attention of the Landscape Architect or Owner's Representative immediately, they may be responsible for the labor and materials associated with correcting the
- 14. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- 15. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- 16. All plants shall be legibly tagged with proper botanical name.
- 17. The Contractor shall guarantee all plants including seeding, for not less than one year from time of acceptance.
- 18. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- 19. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- 20. All landscaping shall be provided with the following:

be located within planting bed areas.

- a. Outside hose attachments spaced a maximum of 150 feet apart, and b. An underground irrigation system, or
- c. A temporary irrigation system designed for a two-year period of plant
- 21. If an automatic irrigation system is installed, all irrigation valve boxes shall
- 22. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, watering of plants, including seeding and weeding. Plants shall be appropriately watered prior to, during, and after planting. It is the Contractor's responsibility to provide clean water suitable for plant health from off site, should it not be available on site.
- 23. Contractor shall provide an alternate price for irrigating all newly landscaped areas and resetting of any existing irrigation that will be disturbed during planting. Contractor shall provide irrigation design for review by
- Landscape Architect or Owner's Representative when awarded the project. 24. All disturbed areas will be dressed with 6" of loam and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- 25. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with one-year-old, well-composted, shredded native bark not longer than 4" in length and ½" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be
- 26. Drip strip shall extend to 6" beyond roof overhang and shall be edged with 3/16" thick metal edger.
- 27. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- 28. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy. Shrubs and ornamental plantings near vehicular travel shall not exceed three feet in height. If pruning is necessary to maintain the required maximum height, plants shall be pruned to a natural form and shall not be sheared.
- 29. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- 30. Landscape Architect is not responsible for the means and methods of the Contractor.



Mulch Ring

(8FT.) diam.

2 times the diameter of the root ball

to be planted shall be no less than

a 3' wide radius from the base of

the tree

Proposed Berm 2.5' ht.

FOR REVIEW

4/32A

- Permeable area in which tree is

with three stakes per tree, spaced evenly

around the trunk with 12 gauge wire. Plastic

hose sections shall be used at attachment to trees. Each wire shall be flagged with a visual

marker. 5' long min. wooden stakes shall be

used to anchor the wires. Stakes shall be

driven at least 12" outside the edge of the planting pit into stable soil. Remove all

staking NO LATER than the end of the first

growing season after planting.-

the site whenever possible.

Mark the north side of the tree in the

nursery. Rotate the tree to face north at

4 in. high earth saucer beyond edge of root

2 IN. max. Mulch. Do NOT place mulch in contact with tree trunk. Maintain the mulch

Tamp soil around root ball base firmly with

Place root ball on unexcavated or tamped

Tree Planting Detail

foot pressure so that root ball does not

weed-free for a minimum of three years

after planting.-

—6" Corrugated PVC tree sock

Each tree must be planted such that the original trunk flare is visible at the top of the root ball. Trees where the original trunk flare is not visible may be rejected. Do NOT cover the top of the root ball with soil. Before planting Contractor shall inspect the rootball for the location of the original root flare. If the original root flare is not visible at the top of the root ball then the Contractor shall then gently remove from the top of the root ball any excess soil from nursery operations that may be covering the original root flare. All secondary and girdling roots shall be removed prior to planting. Trees with 4" or more of extraneous soil and/or adventitious roots greater than 1/8" shall be rejected. The tree shall be planted with the original root flare at or slightly (2-3") above surrounding

finished grade. Backfill with existing soil, in sandy and heavy clay soils

the existing soil. Remove all twine, rope, wire, and burlap

—If plant is shipped with a wire basket around the root ball. prior to planting, the contractor shall cut away the bottom of the wire basket, leaving the sides in place. Once the tree is placed and faced, the contractor shall remove the remainder of the wire basket and backfill the planting pit as

Mulch Ring, typ.

(6)RA

(7) SAW

Remove

Existing Wall

accommodate

New Driveway

Existing Wall

section to

section to

remain

(7)SAW

52.6

Lawn

Grass Bioretention Area

 $(23)Th^{\prime\prime}$ 

Lawn

Proposed
Berm 2.5' ht.

Proposed Square Picket

Existing Wall secton to remain

13269


Fence and Gate

4/28Y/7/35.5/7TT

SOUTH MAIN STREETS

add 20% max. by volume composted organic material to

**Plant List TREES** Common Name **Botanical Name** Symbol Quantity Comments Existing to Remain LS Liquidambar styraciflua American Sweetgum Green Giant Western Red Cedar B&B Thuja plicata 'Green Giant' 8-10' ht B&B UP Ulmus americana 'Princeton' Princeton American Elm 3" cal Betula nigra 'Dura-Heat' Dura-Heat River Birch 10-12' ht Multi-stemmed, B&B SHRUBS Symbol **Botanical Name** Common Name Quantity Comments HY2 Hydrangea macrophylla 'All Summer Beauty' All Summer Beauty Hydrangea (Blue 5 gal hortensia) IG Ilex glabra 'Shamrock' Shamrock Inkberry full to ground 6-7' ht JV Juniperus virginiana 'Emerald Sentinel' Emerald Sentinel Red Cedar **Grow Low Sumac** 5 gal Rhus aromatica 'Grow-Low' 5-6' ht Juniperus scopulorum 'Skyrocket' Skyrocket Juniper Spiraea x bumalda 'Anthony Waterer' Anthony Waterer Spirea 3 gal



Proposed

Walkway

Remove

section to

new walk

24" Existing

*Tree to* 


Remain;


Save and

Protect`

existing wall

accommodate






# )ption Buffer, typ. 4" Existing Tree to Remain; Save and Protect **PROPOSED** BUILDING 36" Existing Tree to $\times$ 48.5 Remain; Save and Protect $\overline{(9)}\overline{Th}$ (9)Ig Drawn By: Proposed 6' Checked By: high board fence , oile. Scale:

WSA RW 1"=20'-0" 2023-05-23 for PB Date: submission Revisions: 2023-07-19 for PB Submission 2023-10-05


2



© 2023 Woodburn & Company Landscape Architecture, LLC

### Landscape Notes

- 1. Design is based on drawings by Beals Associates, PLLC. Drawings may require adjustment due to actual field conditions.
- 2. The contractor shall follow best management practices during construction and shall take all means necessary to stabilize and protect the site from
- 3. Erosion Control shall be in place prior to construction.
- 4. Erosion Control to consist of Hay Bales and Erosion Control Fabric shall be staked in place between the work and Water bodies, Wetlands and/or drainage ways prior to any construction.
- 5. The Contractor shall verify layout and grades and inform the Landscape Architect or Client's Representative of any discrepancies or changes in layout and/or grade relationships prior to construction.
- 6. It is the contractor's responsibility to verify drawings provided are to the correct scale prior to any bid, estimate or installation. A graphic scale bar has been provided on each sheet for this purpose. If it is determined that the scale of the drawing is incorrect, the landscape architect will provide a set of drawings at the correct scale, at the request of the contractor.
- 7. Trees to Remain within the construction zone shall be protected from damage for the duration of the project by snow fence or other suitable means of protection to be approved by Landscape Architect or Client's Representative. Snow fence shall be located at the drip line or at the distance in feet from the trunk equal to the diameter of the tree caliper in inches, whichever is greater, and shall be expanded to include any and all surface roots. Do not fill or mulch on the trunk flare. Do not disturb roots. In order to protect the integrity of the roots, branches, trunk and bark of the tree(s) no vehicles or construction equipment shall drive or park in or on the area within the drip line(s) of the tree(s). Do not store any refuse or construction materials or portalets within the tree protection area.
- 8. This plan is for review purposes only, NOT for Construction. Construction Documents will be provided upon request.
- 9. Location, support, protection, and restoration of all existing utilities and appurtenances shall be the responsibility of the Contractor.
- 10. The Contractor shall verify exact location and elevation of all utilities with the respective utility owners prior to construction. Call DIGSAFE at 811 or 888-DIG-SAFE (1-888-344-7233.)
- 11. The Contractor shall procure any required permits prior to construction.
- 12. Prior to any landscape construction activities Contractor shall test all existing loam and loam from off-site intended to be used for lawns and plant beds using a thorough sampling throughout the supply. Soil testing shall indicate levels of pH, nitrates, macro and micro nutrients, texture, soluble salts, and organic matter. Contractor shall provide Landscape Architect with test results and recommendations from the testing facility along with soil amendment plans as necessary for the proposed plantings to thrive. All loam to be used on site shall be amended as approved by the Landscape Architect prior to placement.
- 13. Contractor shall notify landscape architect or owner's representative immediately if at any point during demolition or construction a site condition is discovered which may negatively impact the completed project. This includes, but is not limited to, unforeseen drainage problems, unknown subsurface conditions, and discrepancies between the plan and the site. If a Contractor is aware of a potential issue and does not bring it to the attention of the Landscape Architect or Owner's Representative immediately, they may be responsible for the labor and materials associated with correcting the
- 14. The Contractor shall furnish and plant all plants shown on the drawings and listed thereon. All plants shall be nursery-grown under climatic conditions similar to those in the locality of the project. Plants shall conform to the botanical names and standards of size, culture, and quality for the highest grades and standards as adopted by the American Association of Nurserymen, Inc. in the American Standard of Nursery Stock, American Standards Institute, Inc. 230 Southern Building, Washington, D.C. 20005.
- 15. A complete list of plants, including a schedule of sizes, quantities, and other requirements is shown on the drawings. In the event that quantity discrepancies or material omissions occur in the plant materials list, the planting plans shall govern.
- 16. All plants shall be legibly tagged with proper botanical name.
- 17. The Contractor shall guarantee all plants including seeding, for not less than one year from time of acceptance.
- 18. Owner or Owner's Representative will inspect plants upon delivery for conformity to Specification requirements. Such approval shall not affect the right of inspection and rejection during or after the progress of the work. The Owner reserves the right to inspect and/or select all trees at the place of growth and reserves the right to approve a representative sample of each type of shrub, herbaceous perennial, annual, and ground cover at the place of growth. Such sample will serve as a minimum standard for all plants of the same species used in this work.
- 19. No substitutions of plants may be made without prior approval of the Owner or the Owner's Representative for any reason.
- 20. All landscaping shall be provided with the following:
- a. Outside hose attachments spaced a maximum of 150 feet apart, and b. An underground irrigation system, or
- c. A temporary irrigation system designed for a two-year period of plant
- 21. If an automatic irrigation system is installed, all irrigation valve boxes shall be located within planting bed areas.
- 22. The contractor is responsible for all plant material from the time their work commences until final acceptance. This includes but is not limited to maintaining all plants in good condition, the security of the plant material once delivered to the site, watering of plants, including seeding and weeding. Plants shall be appropriately watered prior to, during, and after planting. It is the Contractor's responsibility to provide clean water suitable for plant health from off site, should it not be available on site.
- 23. Contractor shall provide an alternate price for irrigating all newly landscaped areas and resetting of any existing irrigation that will be disturbed during planting. Contractor shall provide irrigation design for review by Landscape Architect or Owner's Representative when awarded the project.
- 24. All disturbed areas will be dressed with 6" of loam and planted as noted on the plans or seeded except plant beds. Plant beds shall be prepared to a depth of 12" with 75% loam and 25% compost.
- 25. Trees, ground cover, and shrub beds shall be mulched to a depth of 2" with FOR REVIEW ONLY one-year-old, well-composted, shredded native bark not longer than 4" in length and ½" in width, free of woodchips and sawdust. Mulch for ferns and herbaceous perennials shall be no longer than 1" in length. Trees in lawn areas shall be mulched in a 5' diameter min. saucer. Color of mulch shall be
- 26. Drip strip shall extend to 6" beyond roof overhang and shall be edged with 3/16" thick metal edger.
- 27. In no case shall mulch touch the stem of a plant nor shall mulch ever be more than 3" thick total (including previously applied mulch) over the root ball of any plant.
- 28. Secondary lateral branches of deciduous trees overhanging vehicular and pedestrian travel ways shall be pruned up to a height of 6' to allow clear and safe passage of vehicles and pedestrians under tree canopy. Shrubs and ornamental plantings near vehicular travel shall not exceed three feet in height. If pruning is necessary to maintain the required maximum height, plants shall be pruned to a natural form and shall not be sheared.
- 29. Snow shall be stored a minimum of 5' from shrubs and trunks of trees.
- 30. Landscape Architect is not responsible for the means and methods of the Contractor.



—6" Corrugated PVC tree sock

is visible at the top of the root ball. Trees where the original trunk flare is not visible may be rejected. Do NOT cover the top of the root ball with soil. location of the original root flare. If the original root flare is not visible at the top of the root ball then the Contractor shall then gently remove from the top of the root ball any excess soil from nursery operations that may be covering the original root flare. All secondary and girdling roots shall be removed prior to planting. Trees with 4" or more of extraneous soil and/or adventitious roots greater than 1/8" shall be rejected. The tree shall be planted with the original root flare at or slightly (2-3") above surrounding finished grade.

Each tree must be planted such that the original trunk flare Before planting Contractor shall inspect the rootball for the

Mulch Ring, typ.

(6)RA

(7) SAW

Remove

Existing Wall

accommodate

New Driveway

Existing Wall

section to

section to

remain

(7)SAW

(13)Th

after planting.— Backfill with existing soil, in sandy and heavy clay soils add 20% max. by volume composted organic material to Tamp soil around root ball base firmly with the existing soil. foot pressure so that root ball does not Remove all twine, rope, wire, and burlap

> Proposed Berm 2.5' ht.

4/32A

Mulch Ring

(8FT.) diam.

—If plant is shipped with a wire basket around the root ball. 2 times the diameter of the root ball prior to planting, the contractor shall cut away the bottom - Permeable area in which tree is of the wire basket, leaving the sides in place. Once the to be planted shall be no less than tree is placed and faced, the contractor shall remove the a 3' wide radius from the base of remainder of the wire basket and backfill the planting pit as the tree

Tree Planting Detail

Place root ball on unexcavated or tamped

with three stakes per tree, spaced evenly

around the trunk with 12 gauge wire. Plastic

hose sections shall be used at attachment to trees. Each wire shall be flagged with a visual

marker. 5' long min. wooden stakes shall be

used to anchor the wires. Stakes shall be

driven at least 12" outside the edge of the

staking NO LATER than the end of the first

planting pit into stable soil. Remove all

Mark the north side of the tree in the

nursery. Rotate the tree to face north at

4 in. high earth saucer beyond edge of root


2 IN. max. Mulch. Do NOT place mulch in contact with tree trunk. Maintain the mulch


weed-free for a minimum of three years


growing season after planting.-

the site whenever possible.










# **Optio**a

WSA Drawn By: RW Checked By: 1"=20'-0" Scale: 2023-10-05 Date:

Revisions:

2



4/28Y/7/35.5/7TT

Sheet 1 of 1 © 2023 Woodburn & Company Landscape Architecture, LLC